

Mobile Studios

HD 12-Channel Mobile Video Studio

OBV-3200

| | |
|------------------------------|---|
| Digital Video Switcher | SE-3200 |
| 17.3" Rack Mount LCD | TLM-170VM x2 |
| Recorder | HDR-90 x1 (OBV-3200A) HDR-70 x1, HDR-90 x1 (OBV-3200B) |
| Intercom/Tally System | ITC-300 w/4 Belt Pack |
| SDI Vector Scope | Built-in TLM-170VM |
| Audio Mixer | AD-200 |
| Power Distributor (8-way) | PD-2A |
| Return Video (8-CH CV) | ---- |
| Camera Control System | CCU-200 x1 |
| Camera Power Distributor | ---- |
| Multi-camera Control Unit | MCU-400 / MCU-200 (optional) |
| H.264 Video Streaming Server | NVS-35 x1 (OBV-3200A) NVS-40 x1 (OBV-3200B) |
| 4K Multicamera Processor | ---- |
| Network Media Player | ---- |
| HD/SD SDI Amplifier | ---- |
| Rack System Integration | 17RU Mobile Rack Table 110 x 100 x 111 cm |
| Weight | 118 kg |
| Operating Temp. Range | 0~40 °C |

Options

| | |
|--------------------------|----------------------------|
| Camera Power Distributor | PD-5 |
| Camera Power Regulator | ---- |
| Redundant Power (360W) | ---- |
| SDI/CV/ITC/DC Cable | CB-66 |
| CB-22H/23H Repeater | ---- |
| SDI/ITC Cable | ---- |
| ITC/Tally Cable | ---- |
| HDMI Cable | CB-60/61/62 (30m/50m/100m) |
| 100m SDI Repeater | ---- |

What's in the Box

1 x OBV-3200 product
4 x AD-3 Unit
4 x RMC-240 Unit
5 x Headset
4 x ϕ 3.5 Plug to ϕ 3.5 Plug Cable
4 x ϕ 2.5 Plug to ϕ 3.5 Plug Cable
2 x AC Power Cord
5 x 120mm cable tie
10 x 200mm cable tie
1 x Y type 2 pin MOLEX cable
2 x 2.5" HDD enclosure
2 x ISO screw 2*6mm
4 x Cable & Cable Reel
1 x SATA to USB Cable
2 x HD sticker